TERRACE STORAGE TABLE - 1% - LANDSLOPE

Combined Natural and Filled Storage in Cubic Feet Per Lineal Foot

d \ f	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7	0.8	0.9	1.0	1.1	1.2	1.3	1.4	1.5	1.6	1.7	1.8	1.9	2.0
0.1	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21
0.2	3	5	7	9	11	13	15	17	19	21	23	25	27	29	31	33	35	37	39	41	43
0.3	7	10	13	16	19	22	25	28	31	34	37	40	43	46	49	52	55	58	61	64	67
0.4	11	15	19	23	27	31	35	39	43	47	51	55	59	63	67	71	75	79	83	87	91
0.5	16	21	26	31	36	41	46	51	56	61	66	71	76	81	86	91	96	101	106	111	116
0.6	22	28	34	40	46	52	58	64	70	76	82	88	94	100	106	112	118	124	130	136	142
0.7	29	36	43	50	57	64	71	78	85	92	99	106	113	120	127	134	141	148	155	162	169
0.8	38	46	54	62	70	78	86	94	102	110	118	126	134	142	150	158	166	174	182	190	198
0.9	47	56	65	74	83	92	101	110	119	128	137	146	155	164	173	182	191	200	209	218	227
1.0	57	67	77	87	97	107	117	127	137	147	157	167	177	187	197	207	217	227	237	247	257
1.1	68	79	90	101	112	123	134	145	156	167	178	189	200	211	222	233	244	255	266	277	288
1.2	80	92	104	116	128	140	152	164	176	188	200	212	224	236	248	260	272	284	296	308	320
1.3	94	107	120	133	146	159	172	185	198	211	224	237	250	263	276	289	302	315	328	341	354
1.4	108	122	136	150	164	178	192	206	220	234	248	262	276	290	304	318	332	346	360	374	388
1.5	123	138	153	168	183	198	213	228	243	258	273	288	303	318	333	348	363	378	393	408	423
1.6	139	155	171	187	203	219	235	251	267	283	299	315	331	347	363	379	395	411	427	443	459
1.7	156	173	190	207	224	241	258	275	292	309	326	343	360	377	394	411	428	445	462	479	496
1.8	175	193	211	229	247	265	283	301	319	337	355	373	391	409	427	445	463	481	499	517	535
1.9	194	213	232	251	270	289	308	327	346	365	384	403	422	441	460	479	498	517	536	555	574
2.0	214	234	254	274	294	314	334	354	374	394	414	434	454	474	494	514	534	554	574	594	614
2.1	235	256	277	298	319	340	361	382	403	424	445	466	487	508	529	550	571	592	613	634	655
2.2	257	279	301	323	345	367	389	411	433	455	477	499	521	543	565	587	609	631	653	675	697
2.3	281	304	327	350	373	396	419	442	465	488	511	534	557	580	603	626	649	672	695	718	741
2.4	305	329	353	377	401	425	449	473	497	521	545	569	593	617	641	665	689	713	737	761	785
2.5	330	355	380	405	430	455	480	505	530	555	580	605	630	655	680	705	730	755	780	805	830
2.6	356	382	408	434	460	486	512	538	564	590	616	642	668	694	720	746	772	798	824	850	876
2.7	383	410	437	464	491	518	545	572	599	626	653	680	707	734	761	788	815	842	869	896	923
2.8	412	440	468	496	524	552	580	608	636	664	692	720	748	776	804	832	860	888	916	944	972
2.9	441	470	499	528	557	586	615	644	673	702	731	760	789	818	847	876	905	934	963	992	1021
3.0	471	501	531	561	591	621	651	681	711	741	771	801	831	861	891	921	951	981	1011	1041	1071

NOTES

1. All frontslopes are 14 feet. Stakeline is 14 feet uphill from completed terrace ridge and will be the centerline of completed channel. f -fill in channel in feet.
2. d - depth of water in feet in completed terrace, measured from completed channel bottom to top of terrace ridge. Terrace ridge is assumed to always be at the design depth level, even when f exceeds d. Cutslope is 6:1.

TERRACE STORAGE TABLE - 2% - LANDSLOPE

Combined Natural and Filled Storage in Cubic Feet Per Lineal Foot

d \ f	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7	0.8	0.9	1.0	1.1	1.2	1.3	1.4	1.5	1.6	1.7	1.8	1.9	2.0
0.1	1	1	2	2	3	3	4	4	5	5	6	6	7	7	8	8	9	9	10	10	11
0.2	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22
0.3	4	6	7	9	10	12	13	15	16	18	19	21	22	24	25	27	28	30	31	33	34
0.4	7	9	11	13	15	17	19	21	23	25	27	29	31	33	35	37	39	41	43	45	47
0.5	10	12	15	17	20	22	25	27	30	32	35	37	40	42	45	47	50	52	55	57	60
0.6	13	16	19	22	25	28	31	34	37	40	43	46	49	52	55	58	61	64	67	70	73
0.7	17	21	24	28	31	35	38	42	45	49	52	56	59	63	66	70	73	77	80	84	87
0.8	22	26	30	34	38	42	46	50	54	58	62	66	70	74	78	82	86	90	94	98	102
0.9	27	31	36	40	45	49	54	58	63	67	72	76	81	85	90	94	99	103	108	112	117
1.0	32	37	42	47	52	57	62	67	72	77	82	87	92	97	102	107	112	117	122	127	132
1.1	38	43	49	54	60	65	71	76	82	87	93	98	104	109	115	120	126	131	137	142	148
1.2	44	50	56	62	68	74	80	86	92	98	104	110	116	122	128	134	140	146	152	158	164
1.3	51	58	64	71	77	84	90	97	103	110	116	123	129	136	142	149	155	162	168	175	181
1.4	59	66	73	80	87	94	101	108	115	122	129	136	143	150	157	164	171	178	185	192	199
1.5	67	74	82	89	97	104	112	119	127	134	142	149	157	164	172	179	187	194	202	209	217
1.6	75	83	91	99	107	115	123	131	139	147	155	163	171	179	187	195	203	211	219	227	235
1.7	84	93	101	110	118	127	135	144	152	161	169	178	186	195	203	212	220	229	237	246	254
1.8	94	103	112	121	130	139	148	157	166	175	184	193	202	211	220	229	238	247	256	265	274
1.9	104	113	123	132	142	151	161	170	180	189	199	208	218	227	237	246	256	265	275	284	294
2.0	114	124	134	144	154	164	174	184	194	204	214	224	234	244	254	264	274	284	294	304	314
2.1	125	135	146	156	167	177	188	198	209	219	230	240	251	261	272	282	293	303	314	324	335
2.2	136	147	158	169	180	191	202	213	224	235	246	257	268	279	290	301	312	323	334	345	356
2.3	148	160	171	183	194	206	217	229	240	252	263	275	286	298	309	321	332	344	355	367	378
2.4	161	173	185	197	209	221	233	245	257	269	281	293	305	317	329	341	353	365	377	389	401
2.5	174	186	199	211	224	236	249	261	274	286	299	311	324	336	349	361	374	386	399	411	424
2.6	187	200	213	226	239	252	265	278	291	304	317	330	343	356	369	382	395	408	421	434	447
2.7	201	215	228	242	255	269	282	296	309	323	336	350	363	377	390	404	417	431	444	458	471
2.8	216	230	244	258	272	286	300	314	328	342	356	370	384	398	412	426	440	454	468	482	496
2.9	231	245	260	274	289	303	318	332	347	361	376	390	405	419	434	448	463	477	492	506	521
3.0	246	261	276	291	306	321	336	351	366	381	396	411	426	441	456	471	486	501	516	531	546

NOTES

1. All frontslopes are 14 feet. Stakeline is 14 feet uphill from completed terrace ridge and will be the centerline of completed channel. f -fill in channel in feet.
2. d - depth of water in feet in completed terrace, measured from completed channel bottom to top of terrace ridge. Terrace ridge is assumed to always be at the design depth level, even when f exceeds d. Cutslope is 6:1

TERRACE STORAGE TABLE - 3% - LANDSLOPE

Combined Natural and Filled Storage in Cubic Feet Per Lineal Foot

d \ f	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7	0.8	0.9	1.0	1.1	1.2	1.3	1.4	1.5	1.6	1.7	1.8	1.9	2.0
0.1	1	1	2	2	2	3	3	3	4	4	4	5	5	5	6	6	6	7	7	7	8
0.2	2	3	3	4	5	5	6	7	7	8	9	9	10	11	11	12	13	13	14	15	15
0.3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
0.4	6	7	8	9	11	12	13	15	16	17	19	20	21	23	24	25	27	28	29	31	32
0.5	8	9	11	13	14	16	18	19	21	23	24	26	28	29	31	33	34	36	38	39	41
0.6	10	12	14	16	18	20	22	24	26	28	30	32	34	36	38	40	42	44	46	48	50
0.7	13	15	18	20	22	25	27	29	32	34	36	39	41	43	46	48	50	53	55	57	60
0.8	16	19	22	24	27	30	32	35	38	40	43	46	48	51	54	56	59	62	64	67	70
0.9	20	23	26	29	32	35	38	41	44	47	50	53	56	59	62	65	68	71	74	77	80
1.0	24	27	30	34	37	40	44	47	50	54	57	60	64	67	70	74	77	80	84	87	90
1.1	28	32	35	39	43	46	50	54	57	61	65	68	72	76	79	83	87	90	94	98	101
1.2	32	36	40	44	48	52	56	60	64	68	72	76	80	84	88	92	96	100	104	108	112
1.3	37	42	46	50	55	59	63	68	72	76	81	85	89	94	98	102	107	111	115	120	124
1.4	43	47	52	56	61	66	70	75	80	84	89	94	98	103	108	112	117	122	126	131	136
1.5	48	53	58	63	68	73	78	83	88	93	98	103	108	113	118	123	128	133	138	143	148
1.6	54	59	65	70	75	81	86	91	97	102	107	113	118	123	129	134	139	145	150	155	161
1.7	60	66	71	77	83	88	94	100	105	111	117	122	128	134	139	145	151	156	162	168	173
1.8	67	73	79	85	91	97	103	109	115	121	127	133	139	145	151	157	163	169	175	181	187
1.9	74	80	86	92	99	105	111	118	124	130	137	143	149	156	162	168	175	181	187	194	200
2.0	81	87	94	101	107	114	121	127	134	141	147	154	161	167	174	181	187	194	201	207	214
2.1	88	95	102	109	116	123	130	137	144	151	158	165	172	179	186	193	200	207	214	221	228
2.2	96	103	111	118	125	133	140	147	155	162	169	177	184	191	199	206	213	221	228	235	243
2.3	104	112	120	127	135	143	150	158	166	173	181	189	196	204	212	219	227	235	242	250	258
2.4	113	121	129	137	145	153	161	169	177	185	193	201	209	217	225	233	241	249	257	265	273
2.5	122	130	138	147	155	163	172	180	188	197	205	213	222	230	238	247	255	263	272	280	288
2.6	131	140	148	157	166	174	183	192	200	209	218	226	235	244	252	261	270	278	287	296	304
2.7	140	149	158	167	176	185	194	203	212	221	230	239	248	257	266	275	284	293	302	311	320
2.8	150	160	169	178	188	197	206	216	225	234	244	253	262	272	281	290	300	309	318	328	337
2.9	161	170	180	189	199	209	218	228	238	247	257	267	276	286	296	305	315	325	334	344	354
3.0	171	181	191	201	211	221	231	241	251	261	271	281	291	301	311	321	331	341	351	361	371

NOTES

1. All frontslopes are 14 feet. Stakeline is 14 feet uphill from completed terrace ridge and will be the centerline of completed channel. f - fill in channel in feet.
2. d - depth of water in feet in completed terrace, measured from completed channel bottom to top of terrace ridge. Terrace ridge is assumed to always be at the design depth level, even when f exceeds d. Cutslope is 6:1.

TERRACE STORAGE TABLE - 4% - LANDSLOPE

Combined Natural and Filled Storage in Cubic Feet Per Lineal Foot

d \ f	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7	0.8	0.9	1.0	1.1	1.2	1.3	1.4	1.5	1.6	1.7	1.8	1.9	2.0
0.1	1	1	1	2	2	2	2	3	3	3	3	4	4	4	4	5	5	5	5	6	6
0.2	2	2	3	3	4	4	5	5	6	6	7	7	8	8	9	9	10	10	11	11	12
0.3	3	4	5	5	6	7	8	8	9	10	11	11	12	13	14	14	15	16	17	17	18
0.4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25
0.5	7	8	9	10	12	13	14	15	17	18	19	20	22	23	24	25	27	28	29	30	32
0.6	9	10	12	13	15	16	18	19	21	22	24	25	27	28	30	31	33	34	36	37	39
0.7	11	13	15	16	18	20	22	23	25	27	29	30	32	34	36	37	39	41	43	44	46
0.8	14	16	18	20	22	24	26	28	30	32	34	36	38	40	42	44	46	48	50	52	54
0.9	16	19	21	23	25	28	30	32	34	37	39	41	43	46	48	50	52	55	57	59	61
1.0	20	22	25	27	30	32	35	37	40	42	45	47	50	52	55	57	60	62	65	67	70
1.1	23	26	28	31	34	37	39	42	45	48	50	53	56	59	61	64	67	70	72	75	78
1.2	26	29	32	35	38	41	44	47	50	53	56	59	62	65	68	71	74	77	80	83	86
1.3	30	33	37	40	43	46	50	53	56	59	63	66	69	72	76	79	82	85	89	92	95
1.4	34	38	41	45	48	52	55	59	62	66	69	73	76	80	83	87	90	94	97	101	104
1.5	39	42	46	50	54	57	61	65	69	72	76	80	84	87	91	95	99	102	106	110	114
1.6	43	47	51	55	59	63	67	71	75	79	83	87	91	95	99	103	107	111	115	119	123
1.7	48	52	57	61	65	69	74	78	82	86	91	95	99	103	108	112	116	120	125	129	133
1.8	53	58	62	67	71	76	80	85	89	94	98	103	107	112	116	121	125	130	134	139	143
1.9	58	63	68	73	77	82	87	92	96	101	106	111	115	120	125	130	134	139	144	149	153
2.0	64	69	74	79	84	89	94	99	104	109	114	119	124	129	134	139	144	149	154	159	164
2.1	70	75	80	86	91	96	101	107	112	117	122	128	133	138	143	149	154	159	164	170	175
2.2	76	81	87	92	98	103	109	114	120	125	131	136	142	147	153	158	164	169	175	180	186
2.3	82	88	94	99	105	111	117	122	128	134	140	145	151	157	163	168	174	180	186	191	197
2.4	89	95	101	107	113	119	125	131	137	143	149	155	161	167	173	179	185	191	197	203	209
2.5	96	102	108	114	121	127	133	139	146	152	158	164	171	177	183	189	196	202	208	214	221
2.6	103	109	116	122	129	135	142	148	155	161	168	174	181	187	194	200	207	213	220	226	233
2.7	110	117	124	130	137	144	151	157	164	171	178	184	191	198	205	211	218	225	232	238	245
2.8	118	125	132	139	146	153	160	167	174	181	188	195	202	209	216	223	230	237	244	251	258
2.9	125	133	140	147	154	162	169	176	183	191	198	205	212	220	227	234	241	249	256	263	270
3.0	134	141	149	156	164	171	179	186	194	201	209	216	224	231	239	246	254	261	269	276	284

NOTES

1. All frontslopes are 14 feet. Stakeline is 14 feet uphill from completed terrace ridge and will be the centerline of completed channel. f - fill in channel in feet.
2. d - depth of water in feet in completed terrace, measured from completed channel bottom to top of terrace ridge. Terrace ridge is assumed to always be at the design depth level, even when f exceeds d. Cutslope is 6:1.

TERRACE STORAGE TABLE - 5% - LANDSLOPE

Combined Natural and Filled Storage in Cubic Feet Per Lineal Foot

d \ f	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7	0.8	0.9	1.0	1.1	1.2	1.3	1.4	1.5	1.6	1.7	1.8	1.9	2.0
0.1	1	1	1	1	2	2	2	2	2	3	3	3	3	3	4	4	4	4	4	5	5
0.2	2	2	3	3	3	4	4	5	5	5	6	6	7	7	7	8	8	9	9	9	10
0.3	3	4	5	5	6	7	7	8	8	9	10	10	11	11	12	13	13	14	14	15	16
0.4	4	5	6	7	8	8	9	10	11	12	12	13	14	15	16	16	17	18	19	20	20
0.5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26
0.6	8	9	10	11	13	14	15	16	17	19	20	21	22	23	25	26	27	28	29	31	32
0.7	10	11	13	14	15	17	18	20	21	22	24	25	27	28	29	31	32	34	35	36	38
0.8	12	14	15	17	18	20	22	23	25	26	28	30	31	33	34	36	38	39	41	42	44
0.9	14	16	18	20	22	23	25	27	29	31	32	34	36	38	40	41	43	45	47	49	50
1.0	17	19	21	23	25	27	29	31	33	35	37	39	41	43	45	47	49	51	53	55	57
1.1	20	22	24	26	29	31	33	35	37	40	42	44	46	48	51	53	55	57	59	62	64
1.2	23	25	28	30	32	35	37	40	42	44	47	49	52	54	56	59	61	64	66	68	71
1.3	26	29	31	34	36	39	42	44	47	49	52	55	57	60	62	65	68	70	73	75	78
1.4	29	32	35	38	41	43	46	49	52	55	57	60	63	66	69	71	74	77	80	83	85
1.5	33	36	39	42	45	48	51	54	57	60	63	66	69	72	75	78	81	84	87	90	93
1.6	37	40	43	46	50	53	56	59	62	66	69	72	75	78	82	85	88	91	94	98	101
1.7	41	44	48	51	54	58	61	65	68	71	75	78	82	85	88	92	95	99	102	105	109
1.8	45	49	52	56	59	63	67	70	74	77	81	85	88	92	95	99	103	106	110	113	117
1.9	49	53	57	61	65	68	72	76	80	84	87	91	95	99	103	106	110	114	118	122	125
2.0	54	58	62	66	70	74	78	82	86	90	94	98	102	106	110	114	118	122	126	130	134
2.1	59	63	67	71	76	80	84	88	92	97	101	105	109	113	118	122	126	130	134	139	143
2.2	64	68	73	77	81	86	90	95	99	103	108	112	117	121	125	130	134	139	143	147	152
2.3	69	74	78	83	87	92	97	101	106	110	115	120	124	129	133	138	143	147	152	156	161
2.4	74	79	84	89	94	98	103	108	113	118	122	127	132	137	142	146	151	156	161	166	170
2.5	80	85	90	95	100	105	110	115	120	125	130	135	140	145	150	155	160	165	170	175	180
2.6	86	91	96	101	107	112	117	122	127	133	138	143	148	153	159	164	169	174	179	185	190
2.7	92	97	103	108	113	119	124	130	135	140	146	151	157	162	167	173	178	184	189	194	200
2.8	98	104	109	115	120	126	132	137	143	148	154	160	165	171	176	182	188	193	199	204	210
2.9	104	110	116	122	128	133	139	145	151	157	162	168	174	180	186	191	197	203	209	215	220
3.0	111	117	123	129	135	141	147	153	159	165	171	177	183	189	195	201	207	213	219	225	231

NOTES

1. All frontslopes are 14 feet. Stakeline is 14 feet uphill from completed terrace ridge and will be the centerline of completed channel. f - fill in channel in feet.
2. d - depth of water in feet in completed terrace, measured from completed channel bottom to top of terrace ridge. Terrace ridge is assumed to always be at the design depth level, even when f exceeds d. Cutslope is 6:1.

TERRACE STORAGE TABLE - 6% - LANDSLOPE

Combined Natural and Filled Storage in Cubic Feet Per Lineal Foot

d \ f	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7	0.8	0.9	1.0	1.1	1.2	1.3	1.4	1.5	1.6	1.7	1.8	1.9	2.0
0.1	1	1	1	1	1	2	2	2	2	2	2	3	3	3	3	3	3	4	4	4	4
0.2	2	2	2	3	3	3	4	4	4	5	5	5	6	6	6	7	7	7	8	8	8
0.3	3	3	4	4	5	5	6	6	7	7	8	8	9	9	10	10	11	11	12	12	13
0.4	4	5	5	6	7	7	8	9	9	10	11	11	12	13	13	14	15	15	16	17	17
0.5	6	6	7	8	9	10	11	11	12	13	14	15	16	16	17	18	19	20	21	21	22
0.6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27
0.7	9	10	11	12	14	15	16	17	18	19	21	22	23	24	25	26	28	29	30	31	32
0.8	11	12	14	15	16	18	19	20	22	23	24	26	27	28	30	31	32	34	35	36	38
0.9	13	15	16	18	19	21	22	24	25	27	28	30	31	33	34	36	37	39	40	42	43
1.0	15	17	19	20	22	24	25	27	29	30	32	34	35	37	39	40	42	44	45	47	49
1.1	18	20	21	23	25	27	29	31	32	34	36	38	40	42	43	45	47	49	51	53	54
1.2	20	22	24	26	28	30	32	34	36	38	40	42	44	46	48	50	52	54	56	58	60
1.3	23	25	28	30	32	34	36	38	41	43	45	47	49	51	54	56	58	60	62	64	67
1.4	26	28	31	33	35	38	40	42	45	47	49	52	54	56	59	61	63	66	68	70	73
1.5	29	32	34	37	39	42	44	47	49	52	54	57	59	62	64	67	69	72	74	77	79
1.6	33	35	38	41	43	46	49	51	54	57	59	62	65	67	70	73	75	78	81	83	86
1.7	36	39	42	44	47	50	53	56	59	61	64	67	70	73	76	78	81	84	87	90	93
1.8	40	43	46	49	52	55	58	61	64	67	70	73	76	79	82	85	88	91	94	97	100
1.9	43	47	50	53	56	59	62	66	69	72	75	78	81	85	88	91	94	97	100	104	107
2.0	47	51	54	57	61	64	67	71	74	77	81	84	87	91	94	97	101	104	107	111	114
2.1	51	55	58	62	65	69	72	76	79	83	86	90	93	97	100	104	107	111	114	118	121
2.2	56	59	63	67	70	74	78	81	85	89	92	96	100	103	107	111	114	118	122	125	129
2.3	60	64	68	72	76	79	83	87	91	95	99	102	106	110	114	118	122	125	129	133	137
2.4	65	69	73	77	81	85	89	93	97	101	105	109	113	117	121	125	129	133	137	141	145
2.5	70	74	78	82	86	90	95	99	103	107	111	115	120	124	128	132	136	140	145	149	153
2.6	75	79	83	88	92	96	101	105	109	114	118	122	127	131	135	140	144	148	153	157	161
2.7	80	84	89	93	98	102	107	111	116	120	125	129	134	138	143	147	152	156	161	165	170
2.8	85	90	94	99	104	108	113	118	122	127	132	136	141	146	150	155	160	164	169	174	178
2.9	90	95	100	105	110	115	119	124	129	134	139	144	148	153	158	163	168	173	177	182	187
3.0	96	101	106	111	116	121	126	131	136	141	146	151	156	161	166	171	176	181	186	191	196

NOTES

1. All frontslopes are 14 feet. Stakeline is 14 feet uphill from completed terrace ridge and will be the centerline of completed channel. f -fill in channel in feet.
2. d - depth of water in feet in completed terrace, measured from completed channel bottom to top of terrace ridge. Terrace ridge is assumed to always be at the design depth level, even when f exceeds d. Cutslope is 6:1.

TERRACE STORAGE TABLE - 8% - LANDSLOPE

Combined Natural and Filled Storage in Cubic Feet Per Lineal Foot

d \ f	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7	0.8	0.9	1.0	1.1	1.2	1.3	1.4	1.5	1.6	1.7	1.8	1.9	2.0
0.1	1	1	1	1	1	1	2	2	2	2	2	2	2	2	3	3	3	3	3	3	3
0.2	2	2	2	2	3	3	3	3	4	4	4	4	5	5	5	5	6	6	6	6	7
0.3	3	3	3	4	4	5	5	5	6	6	6	7	7	8	8	8	9	9	9	10	10
0.4	4	4	5	5	6	6	7	7	8	8	9	9	10	10	11	11	12	12	13	13	14
0.5	5	6	6	7	8	8	9	9	10	11	11	12	13	13	14	14	15	16	16	17	18
0.6	6	7	8	9	9	10	11	12	12	13	14	15	15	16	17	18	18	19	20	21	21
0.7	8	9	10	11	11	12	13	14	15	16	17	18	18	19	20	21	22	23	24	25	25
0.8	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30
0.9	11	12	14	15	16	17	18	19	20	21	23	24	25	26	27	28	29	30	32	33	34
1.0	13	15	16	17	18	20	21	22	23	25	26	27	28	30	31	32	33	35	36	37	38
1.1	15	17	18	19	21	22	24	25	26	28	29	30	32	33	35	36	37	39	40	41	43
1.2	17	19	20	22	23	25	26	28	29	31	32	34	35	37	38	40	41	43	44	46	47
1.3	20	21	23	25	26	28	29	31	33	34	36	38	39	41	42	44	46	47	49	51	52
1.4	22	24	26	27	29	31	33	34	36	38	40	41	43	45	47	48	50	52	54	55	57
1.5	25	26	28	30	32	34	36	38	40	41	43	45	47	49	51	53	55	56	58	60	62
1.6	27	29	31	33	35	37	39	41	43	45	47	49	51	53	55	57	59	61	63	65	67
1.7	30	32	34	36	38	41	43	45	47	49	51	53	55	58	60	62	64	66	68	70	72
1.8	33	35	37	40	42	44	46	49	51	53	55	58	60	62	64	67	69	71	73	76	78
1.9	36	38	41	43	45	48	50	52	55	57	60	62	64	67	69	71	74	76	79	81	83
2.0	39	42	44	47	49	52	54	57	59	62	64	67	69	72	74	77	79	82	84	87	89
2.1	42	45	48	50	53	55	58	61	63	66	69	71	74	76	79	82	84	87	90	92	95
2.2	46	48	51	54	57	59	62	65	68	70	73	76	79	81	84	87	90	92	95	98	101
2.3	49	52	55	58	61	64	66	69	72	75	78	81	84	87	89	92	95	98	101	104	107
2.4	53	56	59	62	65	68	71	74	77	80	83	86	89	92	95	98	101	104	107	110	113
2.5	57	60	63	66	69	72	75	78	82	85	88	91	94	97	100	103	107	110	113	116	119
2.6	60	64	67	70	73	77	80	83	86	90	93	96	99	103	106	109	112	116	119	122	125
2.7	64	68	71	75	78	81	85	88	91	95	98	102	105	108	112	115	118	122	125	129	132
2.8	69	72	76	79	83	86	90	93	97	100	104	107	111	114	118	121	125	128	132	135	139
2.9	73	76	80	84	87	91	95	98	102	105	109	113	116	120	124	127	131	134	138	142	145
3.0	77	81	85	89	92	96	100	104	107	111	115	119	122	126	130	134	137	141	145	149	152

NOTES

1. All frontslopes are 14 feet. Stakeline is 14 feet uphill from completed terrace ridge and will be the centerline of completed channel. f - fill in channel in feet.
2. d - depth of water in feet in completed terrace, measured from completed channel bottom to top of terrace ridge. Terrace ridge is assumed to always be at the design depth level, even when f exceeds d. Cutslope is 6:1.

TERRACE STORAGE TABLE - 10% - LANDSLOPE

Combined Natural and Filled Storage in Cubic Feet Per Lineal Foot

d \ f	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7	0.8	0.9	1.0	1.1	1.2	1.3	1.4	1.5	1.6	1.7	1.8	1.9	2.0
0.1	1	1	1	1	1	1	1	1	2	2	2	2	2	2	2	2	2	2	3	3	3
0.2	2	2	2	2	2	3	3	3	3	3	4	4	4	4	4	5	5	5	5	5	6
0.3	3	3	3	3	4	4	4	5	5	5	6	6	6	6	7	7	7	8	8	8	9
0.4	4	4	4	5	5	6	6	6	7	7	8	8	8	9	9	10	10	10	11	11	12
0.5	5	5	6	6	7	7	8	8	9	9	10	10	11	11	12	12	13	13	14	14	15
0.6	6	7	7	8	8	9	10	10	11	11	12	13	13	14	14	15	16	16	17	17	18
0.7	7	8	9	9	10	11	12	12	13	14	14	15	16	16	17	18	19	19	20	21	21
0.8	9	10	10	11	12	13	14	14	15	16	17	18	18	19	20	21	22	22	23	24	25
0.9	10	11	12	13	14	15	16	17	18	18	19	20	21	22	23	24	25	26	27	27	28
1.0	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32
1.1	14	15	16	17	18	19	20	21	23	24	25	26	27	28	29	30	31	32	34	35	36
1.2	16	17	18	19	20	22	23	24	25	26	28	29	30	31	32	34	35	36	37	38	40
1.3	18	19	20	21	23	24	25	27	28	29	31	32	33	34	36	37	38	40	41	42	44
1.4	20	21	22	24	25	27	28	29	31	32	34	35	36	38	39	41	42	43	45	46	48
1.5	22	23	25	26	28	29	31	32	34	35	37	38	40	41	43	44	46	47	49	50	52
1.6	24	26	27	29	30	32	34	35	37	38	40	42	43	45	46	48	50	51	53	54	56
1.7	26	28	30	31	33	35	37	38	40	42	43	45	47	48	50	52	54	55	57	59	60
1.8	29	31	32	34	36	38	40	41	43	45	47	49	50	52	54	56	58	59	61	63	65
1.9	31	33	35	37	39	41	43	45	47	48	50	52	54	56	58	60	62	64	66	67	69
2.0	34	36	38	40	42	44	46	48	50	52	54	56	58	60	62	64	66	68	70	72	74
2.1	37	39	41	43	45	47	49	51	54	56	58	60	62	64	66	68	70	72	75	77	79
2.2	40	42	44	46	48	51	53	55	57	59	62	64	66	68	70	73	75	77	79	81	84
2.3	43	45	47	49	52	54	56	59	61	63	66	68	70	72	75	77	79	82	84	86	89
2.4	46	48	50	53	55	58	60	62	65	67	70	72	74	77	79	82	84	86	89	91	94
2.5	49	51	54	56	59	61	64	66	69	71	74	76	79	81	84	86	89	91	94	96	99
2.6	52	55	57	60	62	65	68	70	73	75	78	81	83	86	88	91	94	96	99	101	104
2.7	55	58	61	63	66	69	72	74	77	80	82	85	88	90	93	96	99	101	104	107	109
2.8	59	62	64	67	70	73	76	78	81	84	87	90	92	95	98	101	104	106	109	112	115
2.9	62	65	68	71	74	77	80	83	86	88	91	94	97	100	103	106	109	112	115	117	120
3.0	66	69	72	75	78	81	84	87	90	93	96	99	102	105	108	111	114	117	120	123	126

NOTES

1. All frontslopes are 14 feet. Stakeline is 14 feet uphill from completed terrace ridge and will be the centerline of completed channel. f - fill in channel in feet.
2. d - depth of water in feet in completed terrace, measured from completed channel bottom to top of terrace ridge. Terrace ridge is assumed to always be at the design depth level, even when f exceeds d.

Cutslope is 6:1.